

Bill of Quatities - Genexpert sites

Location: 54 facilities across 14 States

S/N	FACILITY	DESCRIPTION OF ITEM	QTY	UNIT	UNIT PRICE	AMOUNT
-----	----------	---------------------	-----	------	------------	--------

OGUN STATE

1	PHC AGBADO	TECHNICAL CHECK AND RECONFIGURATION OF INVERTER SYSTEM	1	Unit		
		REPAIR OF INVERTER	1	Unit		
		REPLACE DC BREAKER	1	Unit		
		REPLACE SURGE PROTECTOR	1	Unit		
		LABOUR AND TRANSPORTATION	1	Unit		

ANAMBRA STATE

2	ONC DIAGNOSTIC HEALTH CARE ODEKPE	TECHNICAL CHECK AND RECONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPAIR OF REFRIGERATOR	1	nr		
		REPLACE CHARGE CONTROLLER	1	nr		
		REPLACE DC BREAKER	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
3	ORUMBA GH AJALLI	LABOUR AND TRANSPORTATION	1	nr		
		TECHNICAL CHECK AND RECONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPAIR OF REFRIGERATOR	1	nr		
4	SAINT CHARLES BORROMEO HOSPITAL, ONITSHA	LABOUR AND TRANSPORTATION	1	nr		
		TECHNICAL CHECK AND RECONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACEMENT OF 120A SOLAR CHARGE CONTROLLER	1	nr		
		REPLACEMENT OF INVERTER	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		

OYO STATE

5	GOVT CHEST HOSPITAL JERICHO	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACEMENT OF AC BREAKER	1	nr		
		REPLACEMENT OF DC BREAKER	1	nr		
		REPLACEMENT OF SURGE PROTECTOR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
6	BOWEN UNIVERSITY TEACHING HOSPITAL	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	Unit		
		INSTALL 1HP INVERTER AC	1	Unit		
		INSTALL SOLAR REFRGERATOR	1	Unit		
		LABOUR AND TRANSPORTATION	1	Unit		
7	STATE HOSPITAL OYO	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACEMENT OF 12 INVERTER BATTERIES	1	nr		

7	STATE HOSPITAL OYO	REPLACEMENT OF DC BREAKER	1	nr		
		INSTALL SOLAR REFRIGERATOR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		

LAGOS STATE

8	GENERAL HOSPITAL LAGOS ISLAND	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACEMENT OF INVERTER	1	nr		
		REPLACEMENT OF AC BREAKER	1	nr		
		REPLACEMENT OF DC BREAKER	1	nr		
		REPLACEMENT OF SURGE PROTECTOR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
9	SAINT THERESA' HOSPITAL, AJEROMI	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPAIR OF SOLAR ARRAY STAND	1	nr		
		REPLACEMENT OF FAULTY SOLAR PANELS	5	nr		
		FIXING AND REWIRING OF PANEL ARRAY	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		

RIVERS STATE

10	GENERAL HOSPITAL DEGEMA	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		INSTALLATION ON 220L SOLAR REFRIGERATOR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
11	GENERAL HOSPITAL OKRIKA	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		INSTALL INVERTER AC	1	nr		
		INSTALL SOLAR REFRIGERATOR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
12	GH BORI, KHANA LGA	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPAIR OF AC	1	nr		
		REPLACEMENT OF FAULTY CHARGE CONTROLLER	1	nr		
		REPLACEMENT OF PV DISCONNECT	1	nr		
		REPLACEMENT OF DC BREAKER	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
13	MILLITARY HOSPITAL	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACEMENT OF BROKEN SOLAR PANEL	2	nr		
		REPLACEMENT OF FAULTY CHARGE CONTROLLER	1	nr		
		REPLACEMENT OF PV DISCONNECT	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
		TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACEMENT OF BROKEN/DAMAGED PANEL SOLAR PANEL	10	nr		
		ROOF INSTALLATION OF ARRAY	1	nr		

14	ZONAL HOSPITAL AHOADA	REPLACEMENT OF FAULTY CHARGE CONTROLLER	1	nr		
		REPLACEMENT OF PV DISCONNECT	1	nr		
		REPLACEMENT OF AC BREAKER	1	nr		
		REPLACEMENT OF DC BREAKER	1	nr		
		REWIRING OF SOLAR ARRAY	1	nr		
		REPLACEMENT OF DC COMBINER BOX	1	nr		
		INSTALLATION OF FULL GROUNDING STATION AND CIRCUIT	1	nr		
		REPLACEMENT OF LIGHTENING ARRESTOR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
15	FMC OTUOKE	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPAIR OF AIR CONDITIONER	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
16	MERIDIAN HOSPITAL	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACEMENT OF FAULTY INVERTER	1	nr		
		REPLACEMENT OF CHARGE CONTROLLER	1	nr		
		REPLACE DC BREAKER	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		

CROSS RIVER STATE

17	DLHMH	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACEMENT OF SOLAR REFRIGERATOR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		

ENUGU STATE

18	82 DIV ARMY HOSPITAL	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACE FAULTY CHARGE CONTROLLER	1	nr		
		REPLACE DC BREAKER	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
19	ENUGU EZIKE DISTRICT HOSPITAL	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		INSTALL INVERTER AC	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
		TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACE BROKEN/DAMGED SOLAR ARRAY PANELS	6	nr		

20	ORJI RIVER DISTRICT HOSPITAL	REPLACE FAULTY CHARGE CONTROLLER	1	nr		
		REWIRING OF SOLAR ARRAY	1	nr		
		TRANSLOCATION OF ARRAY TO ROOF INSTALLATION	1	nr		
		REPLACEMENT OF DC COMBINER BOX	1	nr		
		REPLACEMENT OF PV DISCONNECT	1	nr		
		REPLACEMENT OF DC BREAKER	1	nr		
		REPLACEMENT OF AC BREAKER	1	nr		
		REPLACEMENT OF SURGE PROTECTION	1	nr		
		INSTALLATION OF FULL GROUNDING STATION AND CIRCUIT	1	nr		
		REPLACEMENT OF LIGHTENING ARRESTOR	1	nr		
		INSTALL INVERTER AC	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
21	AGBANI DISTRICT HOSPITAL NKANU WEST	FULL OPTIMIZATION				
		Not less than 5KVA DC to AC, Online, Pure sinewave Inverter	1	Unit		
		200AH - 225AH Deep cycle Gel inverter batteries	12	Unit		
		Monocrystalline 400watts - 450watts Solar Panel	18	Unit		
		120amp MPPT Solar Charge Controller	1	Unit		
		1000-10000v Surge protection	1	Unit		
		Solar array stand (Galvanised)	1	Unit		
		Concrete base for solar array stand.	1	Unit		
		AC MCB 120 amps (Inverter Guard)	1	Unit		
		DC MCB 120 amps Dual pole (Battery Guard)	1	Unit		
		DC PV Disconnect 120 amps (Solar Array Guard)	1	Unit		
		Changeover switch 160Amps - 200Amps	1	Unit		
		Battery cables - 35mm ² Single Core Flex, PVC, PCP Cable	20	Unit		
		Load cables: 16 mm ² Three Core Flex nGS, PVC, PCP/EPR Cable	35	Unit		
		Alternate supply cable 16 mm ² three Core RHZ1 non amored Cable.	20	Unit		
		Solar array cables: 25 mm ²	40	Unit		
		25 mm ² bare single core grounding cable	20	Unit		
		Battery rack for 12 200AH - 225AH deep cycle Gel batteries	1	Unit		
		12 way DC Combiner Box	1	Unit		
		220L DC Solar Refrigerator	1	Unit		
6 way Distribution box	1	Unit				
1 hp dual inverter Air Conditioner	1	Unit				

		Solid rod Lightning arrestor (1.5meters exposure)	1	Unit		
		Full Grounding station	1	Lot		
		Termination accessories	1	lot		
		Inland transportation of all equipment to site	1	Unit		
		Complete installation of all equipment	1	Lot		
		Commisioning and testing	1	Lot		
22	OUR LADY HEALTH OF THE SICK, ADANI	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACE CHARGE CONTROLLER	1	nr		
		REPLACE INVERTER	1	nr		
		REPLACE DC BREAKER	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		REPLACE PV DISCONNECT	1	nr		
		INSTALL 10KVA AVR	1	nr		
		SYSTEM WIRING RECONFIGURATION	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
23	ANNOUNCIATION HOSPITAL	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACE CHARGE CONTROLLER	1	nr		
		REPLACE INVERTER	1	nr		
		REPLACE DC BREAKER	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		REPLACE PV DISCONNECT	1	nr		
		INSTALL 10KVA AVR	1	nr		
		SYSTEM WIRING RECONFIGURATION	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
24	GENERAL HOSPITAL IKEM	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPAIR AC	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		

OSUN STATE

25	PHC OKE BAALE	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACE 12 200AH GEL BATTERIES	12	nr		
		REPLACE AC BREAKER	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		INSTALL 10KVA AVR	1	nr		

		REPAIR OF AC	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
26	ADENLE HOSPITAL ILESHA	TECHNICAL INSPECTION AND RECONFIGURATION	1	nr		
		REPLACE AC BREAKER	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		INSTALL 10KVA AVR	1	nr		
		PROVIDE 220L SOLAR REFRIGERATOR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
27	SH IKIRE	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPAIR OF AC	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
28	SH IKRUN	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACE AC BREAKER	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		REPLACE DC BREAKER	1	nr		
		INSTALL 10KVA AVR	1	nr		
		REPAIR OF AC	1	nr		
		PURCHASE AND INSTALL 220L SOLAR REFRIGERATOR	1	nr		
LABOUR AND TRANSPORTATION	1	nr				
29	SSH ASUBAIRO	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPAIR OF AC	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
30	OAUTH	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACE REFRIGERATOR ADAPTER	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
31	VICTORY HOSPITAL IWO	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACE REFRIGERATORE ADAPTER	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
32	BAPTIST HOSPITAL EJIGBO	PROVIDE 220L SOLAR REFRIGERATOR	1	nr		
		TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		SOLAR SYSTEM REWIRING	1	nr		
		INSTALL 10KVA AVR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
		PROVIDE 220L SOLAR REFRIGERATOR	1	nr		

33	SDAH	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		

DELTA STATE

34	CH AGBOR	TECHNICAL INSPECTION AND RCONFIGURATION of INVERTER SYSTEM	1	nr		
		REPLACEMENT OF INVERTER	1	nr		
		REPLACEMENT OF AC BREAKER	1	nr		
		REPLACEMENT OF DC BREAKER	1	nr		
		REPLACEMENT OF SURGE PROTECTOR	1	nr		
		INSTALL 10KVA AVR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		

35	TBL EKU	FULL OPTIMIZATION				
		Not less than 5KVA DC to AC, Online, Pure sinewave Inverter	1	Unit		
		200AH - 225AH Deep cycle Gel inverter batteries	12	Unit		
		Monocrystalline 400watts - 450watts Solar Panel	18	Unit		
		120amp MPPT Solar Charge Controller	1	Unit		
		1000-10000v Surge protection	1	Unit		
		Solar array stand (Galvanised)	1	Unit		
		Concrete base for solar array stand.	1	Unit		
		AC MCB 120 amps (Inverter Guard)	1	Unit		
		DC MCB 120 amps Dual pole (Battery Guard)	1	Unit		
		DC PV Disconnect 120 amps (Solar Array Guard)	1	Unit		
		Changeover switch 160Amps - 200Amps	1	Unit		
		Battery cables - 35mm ² Single Core Flex, PVC, PCP Cable	20	Unit		
		Load cables: 16 mm ² Three Core Flex nGS, PVC, PCP/EPR Cable	35	Unit		
		Alternate supply cable 16 mm ² three Core RHZ1 non amored Cable.	20	Unit		
		Solar array cables: 25 mm ²	40	Unit		
		25 mm ² bare single core grounding cable	20	Unit		
		Battery rack for 12 200AH - 225AH deep cycle Gel batteries	1	Unit		
		12 way DC Combiner Box	1	Unit		
		220L DC Solar Refrigerator	1	Unit		
6 way Distribution box	1	Unit				
1 hp dual inverter Air Conditioner	1	Unit				
Solid rod Lightning arrestor (1.5meters exposure)	1	Unit				
Full Grounding station	1	Lot				

		Termination accessories	1	lot		
		Inland transportation of all equipment to site	1	Unit		
		Complete installation of all equipment	1	Lot		
		Commisioning and testing	1	Lot		
36	CH SAPELE	TECHNICAL INSPECTION AND CONFIGURATION OF	1	nr		
		INSTALL SOLAR REFRIGERATOR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
37	CH UGHELLI	TECHNICAL INSPECTION AND CONFIGURATION OF	1	nr		
		REPAIR OF REFRIGERATOR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		

BAYELSA STATE

38	TBL REFERENCE HOSPITAL IGBOEGENE	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		PROVIDE INVERTER AC	1	nr		
		INSTALL 10KVA AVR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
39	FMC OTUOKE	TECHNICAL INSPECTION AND CONFIGURATION OF	1	nr		
		REPAIR INVERTER AC	1	nr		
		INSTALL 10KVA AVR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
40	FAMILY CARE HOSPITAL	TECHNICAL INSPECTION AND CONFIGURATION OF	1	nr		
		REPLACE FAULTY CHARGE CONTROLLER	1	nr		
		REPLACE INVERTER	1	nr		
		REPLACE DC BREAKER	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		REPLACE PV DISCONNECT	1	nr		
		INSTALL 10KVA AVR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
41	GH NEMBE	TECHNICAL INSPECTION AND CONFIGURATION OF INVERTER SYSTEM	1	nr		
		REPLACE REFRIGERATOR ADAPTER	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		

PLATEAU STATE

42	CHRC MANGU	TECHNICAL INSPECTION AND CONFIGURATION OF	1	nr		
		REPLACE INVERTER	1	nr		
		REPLACE AC BREAKER	1	nr		
		REPLACE DC BREAKER	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		INSTALL 10KVA AVR	1	nr		

		LABOUR AND TRANSPORTATION	1	nr		
43	NIG AIRFORCE HOSPITAL	TECHNICAL INSPECTION AND CONFIGURATION OF	1	nr		
		REPAIR INVERTER AC	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
44	PSSH JOS	TECHNICAL INSPECTION AND CONFIGURATION OF	1	nr		
		REPLACE PV DISCONNECT	1	nr		
		REPLACE DC BREAKER	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		REPLACE AC BREAKER	1	nr		
		INSTALL 10KVA AVR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		

ABIA STATE

45	SEZTBRL AMACHARA, UMUAHIA	TECHNICAL INSPECTION AND RECONFIGURATION	1	nr		
		REPLACE INVERTER	1	nr		
		REPLACE AC BREAKER	1	nr		
		REPLACE PV DISCONNECT	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		REPLACE DC BREAKER	1	nr		
		INSTALL 10KVA AVR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
46	DONOKEM HOSPITAL UKWA WEST	TECHNICAL INSPECTION AND RECONFIGURATION	1	nr		
		REPLACE BATTERIES	12	nr		
		REPLACE DC BREAKER	1	nr		
		REPLACE PV DISCONNECT	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		INSTALL 10KVA AVR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		

AKWA IBOM STATE

47	IMMACULATE HEART HOSPITAL EKET	TECHNICAL INSPECTION AND RECONFIGURATION	1	nr		
		REPAIR REPLACE BATTERIES	12	nr		
		REPLACE DC BREAKER	1	nr		
		REPLACE PV DISCONNECT	1	nr		
		REPLACE AC BREAKER	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		INSTALL 10KVA AVR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
48	GH IQUITA ORON	TECHNICAL INSPECTION AND RECONFIGURATION	1	nr		
		REPLACEMENT OF DISCONNECT/DAMAGED ARRAY PANELS	6	nr		
		REWIRING OF SOLAR ARRAY	1	nr		
		REPLACE PV DISCONNECT	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		

		REPLACE DC BREAKER	1	nr		
		INSTALL 10KVA AVR	1	nr		
		INSTALL INVERTER AC	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
49	GH IKOT OKORO	TECHNICAL INSPECTION AND RECONFIGURATION	1	nr		
		REPLACEMENT OF DISLOCATED/DAMAGED ARRAY PANELS	6	nr		
		REWIRING OF SOLAR ARRAY	1	nr		
		REPLACE PV DISCONNECT	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		REPLACE DC BREAKER	1	nr		
		INSTALL 10KVA AVR	1	nr		
		INSTALL INVERTER AC	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
50	IDH IKOT EKPEBNE	TECHNICAL INSPECTION AND	1	nr		
		REPLACE INVERTER	1	nr		
		REPLACE CHARGE CONTROLLER	1	nr		
		REPLACE PV DISCONNECT	1	nr		
		REPLACE DC BREAKER	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		REPLACE PV DISCONNECT	1	nr		
		INSTALL 10KVA AVR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
51	SAINT MARY HOSPITAL URUAKPAN	TECHNICAL INSPECTION AND RECONFIGURATION	1	nr		
		REPAIR AC	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
52	UNIV. OF UYO TEACHING HOSPITAL	TECHNICAL INSPECTION AND RECONFIGURATION OF INVERTER SYSTEM	1	nr		
		INSTALL INVERTER AC	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		

IMO STATE

53	GH AWOMMAMMA	TECHNICAL INSPECTION AND RECONFIGURATION	1	nr		
		REPLACE DC BREAKER	1	nr		
		REPLACE PV DISCONNECT	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		REPLACE SOLAR REFRIGERATOR 220L	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		
54	IMO STATE SPECIALIST HOSPITAL OWERRI WEST	TECHNICAL INSPECTION AND RECONFIGURATION	1	nr		
		REPLACEMENT OF BATTERIES	12	nr		
		REPLACE INVERTER	1	nr		
		REWIRING OF SOLAR ARRAY	1	nr		
		REPLACE PV DISCONNECT	1	nr		
		REPLACE SURGE PROTECTOR	1	nr		
		REPLACE DC BREAKER	1	nr		
		INSTALL 10KVA AVR	1	nr		
		LABOUR AND TRANSPORTATION	1	nr		



